



higher education  
& training  
Department:  
Higher Education and Training  
REPUBLIC OF SOUTH AFRICA



**BUFFALO CITY**  
**TVET COLLEGE**

## **REQUEST FOR QUOTATION: RENOVATION AT TRANSPORT OFFICE**

Kindly see the attached request for quote (RFQ). Quotations should be forwarded to [quotations@bccollege.co.za](mailto:quotations@bccollege.co.za).

**TENDERERS MUST NOTE THAT WHEREVER THIS DOCUMENT REFERS TO ANY PARTICULAR TRADE MARK, NAME, PATENT, DESIGN, TYPE, SPECIFIC ORIGIN OR PRODUCER, SUCH REFERENCE SHALL BE DEEMED TO BE ACCOMPANIED BY THE WORDS 'OR EQUIVALENT.**

Kindly submit the following **REQUIRED** documents when responding to the RFQ

- Signed quotation (quotations not signed will be eliminated)
- Latest declaration forms (SBD 4, 8 and 9), see attached on college website
- Certified BBBEE certificate (0 points will be awarded for BBBEE certificates that are not certified)
- Valid Tax Clearance Certificate
- CSD report
- Company Registration
- Bank Confirmation Letter (not older than 3 months)
- Quotations must be detailed as per specification
- All quotations submitted via email addresses other than the one listed above will not be considered.
- **Compulsory briefing will be held on 25 April 2023 at Admin centre, @ 10 am.**

**Closing Date 03 MAY 2023 at 12:00 Pm. No late or hand delivered documents will be accepted. ONLY EMAILED DOCUMENTS WILL BE ACCEPTED**

Enquiries: Ms Thembakazi Mati

043 704 9280 / 043 704 9241

---



**higher education  
& training**  
Department:  
Higher Education and Training  
REPUBLIC OF SOUTH AFRICA



**BUFFALO CITY  
TVET COLLEGE**

Relevant Vocational Education for Changing World

**SPECIFICATION RENOVATION OF TRANSPORT OFFICE**


Requires. CIDB-1GB or Higher

Enquiries: [nngxekapa@bccollege.co.za](mailto:nngxekapa@bccollege.co.za)

Date: 30/03/2023

NO	ITEM	DESCRIPTION	UNIT MEASURE	QUANTITY
1.	Painting	Prepare walls and ceiling to a smooth finish	M <sup>2</sup>	73.74
		Apply dump sealer in to the dump area	M <sup>2</sup>	54.96
		Apply three coat of Plascon paint	M <sup>2</sup>	62.16
2.	floor	Remove floor rug	M <sup>2</sup>	18
		Install new under floor heating	M <sup>2</sup>	28
		Install new Burberry beige polished porcelain tile	M <sup>2</sup>	28
		Install new 75mm aluminium skirting	M	36
		Rubber on the stairs	No	3
3.	Electricity	Install three electric wall box for plugs	No	3
		Electric wire must run in trunking case of 20mm run in top of the skirting	M	12
		Double Plugs must be in a wall box and be mounted to the wall	No	3
		Remove the existing lights and install new LED lights	No	4
		Install new 12000 BTU air conditioner	No	1
4.	Plumbing	Remove existing water pipes for showers	No	1
		Remove the existing water channels	M	2
		Remove old shower trap and install new trap	No	1
		Install new tile	M <sup>2</sup>	3
		Install new cobra junior mix flush system	No	1
		Install new 100 litre geyser wall mounting	No	1
		Install 400 diameter hand basin including water inlet with a mix water tap and cobra junior trap and outlet	No	1

		installed isolator and the air conditioner		
4.	Plumbing	Remove existing water pipes for showers	No	1
		Remove the existing water channels	M	2
		Remove old shower trap and install new trap	No	1
		Install new tile	M <sup>2</sup>	3
		Install new cobra junior mix flush system	No	1
		Install new 100 litre geyser wall mounting	No	1
		Install 400 diameter hand basin including water inlet with a mix water tap and cobra junior trap and outlet	No	1
		Install new 500mmx 600mm mounted mirror	No	1
		Install new soap holder mounted to the wall inside the shower	No	1
		Supply compliance certificate for electricity (CoC), air condition (Certificate of Conformity for gas handling) and geyser (CoC)	No	1
5.	Doors	Prepare doors for paint	No	3
		Paint doors in and out with three coat of gloss paint	No	3

  
\_\_\_\_\_

N. Ngxekana

AD: Infrastructure

Date: 30/03/2023

  
\_\_\_\_\_

Z. Chola

DP: corporate services

Date: 03/03/2023

  
\_\_\_\_\_

Z. Jikwana

AD: SCM

Date: 17/04/2023