



higher education  
& training  
Department  
Higher Education and Training  
REPUBLIC OF SOUTH AFRICA



**BUFFALO CITY**  
**TVET COLLEGE**

## **REQUEST FOR QUOTATION: TOILET FACILITIES (JKB)**

Kindly see the attached request for quote (RFQ). Quotations should be forwarded to [quotations@bccollege.co.za](mailto:quotations@bccollege.co.za).

**TENDERERS MUST NOTE THAT WHEREVER THIS DOCUMENT REFERS TO ANY PARTICULAR TRADE MARK, NAME, PATENT, DESIGN, TYPE, SPECIFIC ORIGIN OR PRODUCER, SUCH REFERENCE SHALL BE DEEMED TO BE ACCOMPANIED BY THE WORDS 'OR EQUIVALENT.**

Kindly submit the following **REQUIRED** documents when responding to the RFQ

- Signed quotation (quotations not signed will be eliminated)
- Declaration forms (SBD 4, 8 and 9)
- Certified BBBEE certificate (0 points will be awarded for BBBEE certificates that are not certified)
- Valid Tax Clearance Certificate
- CSD report
- Company Registration
- Bank Confirmation Letter (not older than 3 months)
- Quotations must be detailed as per specification
- All quotations submitted via email addresses other than the one listed above will not be considered.
- Compulsory briefing will be held on 04 April 2023 at John Knox Bokwe Campus,  
@ 9 am

**Closing Date 17 April 2023 at 12:00 Pm. No late or hand delivered documents will be accepted. ONLY EMAILED DOCUMENTS WILL BE ACCEPTED**

Enquiries: Ms Thembakazi Mati

043 704 9280 / 043 704 9241

---



**higher education  
& training**  
Department:  
Higher Education and Training  
REPUBLIC OF SOUTH AFRICA



**BUFFALO CITY  
TMT COLLEGE**

Date: 07 February 2023

Enquiries: [nngxekana@bccollege.co.za](mailto:nngxekana@bccollege.co.za)

Delivery Date : (within two week from issuing of purchase order)

CIDB GRADING: 1GB PE or higher may apply

All service providers to use this as a pricing document and must submit formal quotes in line with the document below:

**SPECIFICATION FOR TOILET FACILITIES AT JKB**

Number	Item	Scope of works	Unit	Quantity	RATE	TOTAL
<b>Venue 5.5</b>						
1	Removal of existing water closet (Toilet)	<ul style="list-style-type: none"><li>• Disconnect all water supply</li><li>• Remove the existing water closet</li></ul>	Each	2		
2	Installation of WC	<ul style="list-style-type: none"><li>• Installation of a complete junior Flush Master (premium quality to meet heavy traffic use)</li></ul>	Each	2		
3	Painting – Floors	<ul style="list-style-type: none"><li>• All floors to be thoroughly prepared to receive new floor coating</li></ul>	M <sup>2</sup>	34.2		

		<ul style="list-style-type: none"> <li>• Apply two coats of polyurethane on floors as per the recommended factory application</li> </ul>				
4	Painting – Walls	<ul style="list-style-type: none"> <li>• Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>• Apply two coats to an even finish of premium quality similar/ existing colour scheme internal wall paint.</li> </ul>	M <sup>2</sup>	80.64		
5	Painting - Ceilings	<ul style="list-style-type: none"> <li>• Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>• Apply two coats to an even finish of premium quality similar/ existing colour scheme ceiling paint.</li> </ul>	M <sup>2</sup>	34.2		

Number	Item	Scope of works	Unit	Quantity
6	Painting – Doors & Trims	<ul style="list-style-type: none"> <li>Prepare the surface of all doors and trims to a smooth, even finish, and apply two coats of premium wood primer.</li> <li>Apply two coats of premium white gloss paint.</li> </ul>	Each	4
<b>Venue 5.4</b>				
7	Removal of existing water closet (Toilet)	<ul style="list-style-type: none"> <li>Disconnect all water supply</li> <li>Remove the existing water closet</li> </ul>	Each	2
8	Installation of WC	<ul style="list-style-type: none"> <li>Installation of a complete junior Flush Master (premium quality to meet heavy traffic use)</li> </ul>	Each	2
9	Plumbing: Piping (Venue 5.4 & 5.5)	<ul style="list-style-type: none"> <li>Replace existing copper piping with 22mm Copper</li> </ul>	M	10
	Elbows	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	10

	T-Piece	<ul style="list-style-type: none"> <li>• Repalce with 22mm copper</li> </ul>	Each	4		
	Stop - Cock	<ul style="list-style-type: none"> <li>• Replace with 22mm copper</li> </ul>	Each	4		
10	Painting – Floors	<ul style="list-style-type: none"> <li>• All floors to be thoroughly prepared to receive new floor coating</li> <li>• Apply two coats of polyurethane on floors as per the recommended factory application</li> </ul>	M <sup>2</sup>	27.36		
11	Painting – Walls	<ul style="list-style-type: none"> <li>• Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>• Apply two coats to an even finish of premium quality similar/ existing colour scheme internal wall paint.</li> </ul>	M <sup>2</sup>	70.4		
12	Painting Ceilings	<ul style="list-style-type: none"> <li>• Prepare the surface of any cracks and imperfections,</li> </ul>	M <sup>2</sup>	70.4		

		<ul style="list-style-type: none"> <li>• apply two coats of premium quality primer</li> <li>• Apply two coats to an even finish of premium quality similar/ existing colour scheme ceiling paint paint.</li> </ul>				
13	Painting – Doors & Trims	<ul style="list-style-type: none"> <li>• Prepare the surface of all doors and trims to a smooth, even finish, and apply two coats of premium wood primer.</li> <li>• Apply two coats of premium white gloss paint.</li> </ul>	Each	4		
<b>Venue 10</b>						
14	Removal of existing water closet (Toilet)	<ul style="list-style-type: none"> <li>• Disconnect all water supply</li> <li>• Remove the existing water closet</li> </ul>	Each	7		
15	Installation of WC	<ul style="list-style-type: none"> <li>• Installation of a complete junior Flush Master</li> </ul>	Each	7		

Number	Item	Scope of works	Unit	Quantity
16	Plumbing: Piping (Venue 5.4 & 5.5)	<ul style="list-style-type: none"> <li>Replace existing copper piping with 22mm Copper</li> </ul>	M	20
	Elbows	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	10
	T-Piece	<ul style="list-style-type: none"> <li>Repalce with 22mm copper</li> </ul>	Each	7
	Stop - Cock	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	8
<b>Venue 3.8</b>				
17	Removal of existing water closet (Toilet)	<ul style="list-style-type: none"> <li>Disconnect all water supply</li> <li>Remove the existing water closet</li> </ul>	Each	4
18	Installation of WC	<ul style="list-style-type: none"> <li>Installation of a complete junior Flush Master (premium quality to meet heavy traffic use)</li> </ul>	Each	4
19	Plumbing Piping	<ul style="list-style-type: none"> <li>Replace existing copper piping with 22mm Copper</li> </ul>	M	5

	Elbows	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	15		
	T Piece	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	3		
	Stop Cock	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	4		
70	Painting – Walls	<ul style="list-style-type: none"> <li>Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>Apply two coats to an even finish of premium quality similar/ existing colour scheme internal wall paint.</li> </ul>	M <sup>2</sup>	24		
23	Painting Ceilings	<ul style="list-style-type: none"> <li>Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>Apply two coats to an even finish of premium quality similar/ existing</li> </ul>	M <sup>2</sup>	50.7		



		colour scheme ceiling paint paint.			
22	Painting – Doors & Trims	<ul style="list-style-type: none"> <li>Prepare the surface of all doors and trims to a smooth, even finish, and apply two coats of premium wood primer.</li> <li>Apply two coats of premium white gloss paint.</li> </ul>	Each	6	
23	Electrical	<ul style="list-style-type: none"> <li>Remove existing electrical light fitting and switch.</li> <li>Install round shaped (no less than 200mm) 6W LED fitting and PVC switch</li> </ul>	Each	4	
<b>Venue A2</b>					
24	Removal of existing water closet (Toilet)	<ul style="list-style-type: none"> <li>Disconnect all water supply</li> <li>Remove the existing water closet</li> </ul>	Each	6	
25	Installation of W/C	<ul style="list-style-type: none"> <li>Installation of a complete junior</li> </ul>	Each	6	

		Flush Master (premium quality to meet heavy traffic use)		
26	Plumbing: Piping	<ul style="list-style-type: none"> <li>Replace existing copper piping with 22mm Copper</li> </ul>	M	6
	Elbows	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	9
	T Piece	<ul style="list-style-type: none"> <li>Repace with 22mm copper</li> </ul>	Each	7
	Stop Cock	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	6
27	Painting – Walls	<ul style="list-style-type: none"> <li>Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>Apply two coats to an even finish of premium quality similar/ existing colour scheme</li> </ul>	M	54
28	Painting Ceilings	<ul style="list-style-type: none"> <li>Prepare the surface of any cracks and imperfections, apply two coats of</li> </ul>	M <sup>2</sup>	50.4

Number	Item	Scope of works	Unit	Quantity
29	Painting - Doors & Trims	<ul style="list-style-type: none"> <li>• Apply two coats to an even finish of premium quality similar/ existing colour scheme ceiling paint paint.</li> <li>• Prepare the surface of all doors and trims to a smooth, even finish, and apply two coats of premium wood primer</li> <li>• Apply two coats of premium white gloss paint</li> </ul>	Each	2
<b>Venue A1</b>				
30	Removal of existing water closet (Toilet)	<ul style="list-style-type: none"> <li>• Disconnect all water supply</li> <li>• Remove the existing water closet</li> </ul>	Each	8
31	Installation of WC	<ul style="list-style-type: none"> <li>• Installation of a complete junior Flush Master (premium quality)</li> </ul>	Each	8

			to meet heavy traffic use)		
32	Plumbing: Piping	<ul style="list-style-type: none"> <li>Replace existing copper piping with 22mm Copper</li> </ul>	M	8	
	Elbows	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	10	
	T-Piece	<ul style="list-style-type: none"> <li>Repalce with 22mm copper</li> </ul>	Each	7	
	Stop - Cock	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	8	
33	Painting – Walls	<ul style="list-style-type: none"> <li>Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>Apply two coats to an even finish of premium quality similar/ existing colour scheme internal wall paint.</li> </ul>	M	50.4	
34	Painting - Ceilings	<ul style="list-style-type: none"> <li>Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> </ul>	M <sup>2</sup>	32	

35	Painting – Doors & Trims	<ul style="list-style-type: none"> <li>• Apply two coats to an even finish of premium quality similar/ existing colour scheme ceiling paint paint</li> <li>• Prepare the surface of all doors and trims to a smooth, even finish, and apply two coats of premium wood primer</li> <li>• Apply two coats of premium white gloss paint.</li> </ul>	Each	1
36	Preliminary & General	<ul style="list-style-type: none"> <li>• Allow 15 % of total cost of project for P&amp;G</li> </ul>	Item	1
		Sub total		
		VAT		
		Grand total		